Question 8.12

Topic: Timing Requirements for Flow RATAs

Question: In what time-frame must a multiple-load flow RATA be completed?

Answer: Section 6.5(e) of Appendix A, states that each single-load RATA should be completed within 168 consecutive unit or stack operating hours. For multi-load flow RATAs, up to 720 consecutive unit or stack operating hours are allowed to complete the testing at all load levels.

References: Appendix A, Section 6.5(e)

History: First published in March 1995, Update #5; revised in October 1999 Revised Manual; revised in October 2003 Revised Manual