

Question 20.6

Topic: QA Requirements

Question: What are the quality assurance requirements for the monitoring systems installed on the nonaffected unit(s) in a subtractive stack configuration?

Answer: The monitoring systems for the nonaffected unit(s) in a subtractive stack configuration must be fully certified in accordance with § 75.20 and must undergo the periodic quality assurance testing required under § 75.21 and Appendix B to Part 75. The bias test requirement in Section 7.6 of Appendix A to Part 75 also applies to the SO₂, NO_x, and flow rate monitoring systems installed on nonaffected units.

References: § 75.20, § 75.21; Appendix A, Section 7.6

History: First published in March 2000, Update #12