## **Question 11.4**

**Topic:** Timing of Tests

Question: Must the 7-day calibration error test and the linearity test be conducted at

the same time as the RATA?

**Answer:** No. In fact, EPA recommends that utility sources complete the required certification tests in the following order:

- 1. the DAHS verification tests,
- 2. the cycle time test,
- 3. the linearity check,
- 4. the 7-day calibration error test,
- 5. and the RATA.

References: Appendix A, Section 6.1

**History:** First published in Original March 1993 Policy Manual; revised in 2013 Manual