

Question 22.6

Topic: QA Requirements

Question: When common stack NO_x apportionment is used, what are the quality assurance requirements for monitoring systems installed in the duct(s) leading from NO_x nonaffected unit(s) or non-Acid Rain unit(s) to the common stack?

Answer: The monitoring systems located at the NO_x nonaffected unit or non-Acid Rain unit must be fully certified in accordance with testing required under § 75.21 and Appendix B to 40 CFR Part 75. The bias test requirement in Section 7.6 of Appendix A to 40 CFR Part 75 also applies to NO_x and flow rate monitoring systems installed on NO_x nonaffected units.

References:

History: First published in March 2000, Update #12